Legend:

1	IN-SITU CONCRETE BRUSH FINISH (150mm depth)
2	PORFIDO CUBETTI (LIGHT BROWN TAN) 100mm width x 100mm length x 80mm depth
3	PORFIDO CUBETTI (LIGHT RED TAN) 100mm width x 100mm length x 80mm depth
4	HARD LIMESTONE BORDERS
5	PORFIDO PATTERNED PAVING
6	HARD LIMESTONE
B	BOLLARD
L	LITTER BIN
R B	REMOVABLE BOLLARD
F	Replanted FICUS NITADA
L	Acanthus mollis
R T	UPROOTING OF EXISTING FICUS NITADA TO BE REPLANTED

BLISTER TACTILE PAVING

The proposed paving shall not result in any gaps, and provides an even surface that does not hinder the mobility of persons with disability. Particular attention shall be paid to the difficulty that uneven surfaces pose to wheelchair users and persons with ambulatory disabilities. All joints/deges of individual paving blocks will be flush providing an even and smooth surface with no ridges. Joints shall be filled to top surface of the paving slabs. There shall be no ridges in paving surfaces.

/2, BOLOGNA APTS,
TRIQ DUN MICHELE BALZAN,
ATTARD ATD 2980
robert grech
B.E.&A.(HONS) A.&C.E.
MOB: 79463114 TEL:21422404
ARCHITECT & CIVIL ENGINEER

Project Title: MINOR AMENDMENT TO PA 1458/09 PJAZZA SAN PIETRU SAN PAWL NADUR	Drawing No.: NDR22B-01-13	Job No.: 668	CLIENT No.: 236
		DRAWN: JM	CHECKED: RG
Drawing Title: PROPOSED LAYOUT PLAN - REMOVAL OF PALM TREES/INCLUSION OF SIGNAGE	Date: 17/09/2013	Scale: 1: 100	Paper Size: A1

THIS DRAWING IS THE COPYRIGHT OF PERIT ROBERT GRECH & UNAUTHORISED RE-USE OR COPYING IN WHOLE OR IN PART IS PROHIBITED
© Perit Robert Grech
This document has been extracted from the MEPA online system.
DocStatus: Valid; Minor Amendment Approved;
Printed on:17-Mar-2014 10:58803Doc Ref:PA01458/09I41b